



SPANISH FORK NATIONAL GUARD ARMORY RE-ROOF

Municipals Project



PROJECT DESCRIPTION:

- ◆ At this site, the Utah State Department of Facilities Construction and Management (DFCM) was in the process of renovating the existing structure due to contamination from faulty mechanical systems. During this process they determined that much of the finishes on the structure would require replacement, including the roofing.
- ◆ We met with the DFCM Project Manager and the contractor currently assigned to complete the interior work. We then coordinated our design efforts with their construction schedule and consulted with the mechanical sub-contractor to assure protection of any systems designated to remain and to repair any roof penetrations now deemed unnecessary because of the renovation.
- ◆ We replaced the entire single-ply membrane system with new, including raising mechanical units to provide adequate flashing at all mechanical curbs.



Carl Greene
Email: carl@mcneileng.com
801-255-7700 x. 118